

Test Report for CMU Water Uptake Test

Client: Grace Construction Products
Address: 62 Whittemore Ave.
Cambridge, MA 02140

Lab Proj. No: 14-327
Report Date: 5/25/2014

Voucher Number: **DB148985**
Unit Designation/Description: **Coupons**

Sampling Party: Newtonbrook Block & Supply
(Gormley)
Date Tested: 5/22/2014

Physical Properties

(These values are similar to ASTM C140/C140M-14 properties, but they CANNOT be used to show compliance to ASTM C90-14)


Density, lb/ft ³	138.9	138.5	137.9	Avg. Density	138.4	lb/ft ³
Ultimate Density*, lb/ft ³	152.1	152.8	151.6	Avg. Ult. Density	152.2	lb/ft ³
Absorption, lb/ft ³	5.4	5.9	5.6	Avg. Absorption	5.6	lb/ft ³
Absorption, %	3.9	4.2	4.1	Avg. Absorption	4.1	%
Equivalent thickness, (T _e , in.)	1.4	1.5	1.4	Avg. T _e	1.5	in.
Equivalent thickness, (T _e , mm)	35.8	39.3	35.5	Avg. T _e	36.8	mm
Moisture Content at T = 0, %	1.5	1.4	1.2	Avg. % Moisture	1.4	%

* Ultimate density is the theoretical calculated density assuming the CMU was completely consolidated with no voids or absorption. It provides an indication of the consistency of the raw materials used in the CMU production. Ultimate Density, lb/ft³ = Density, lb/ft³ / (1 - (Absorption, lb/ft³ / 62.4)) = [W_d / (W_d - W_i)] x 62.4

Relative Water Uptake of the Unit in Percent of Total Saturation, %U_T, (T in Hours)

Time in Hours	0.00	0.25	1.00	4.00	24.00
Unit #1	0.0	4.5	8.0	12.1	22.2
Unit #2	0.0	3.8	7.0	10.8	21.1
Unit #3	0.0	4.3	7.8	11.5	22.5
Average	0.0	4.2	7.6	11.5	21.9

%U₂₄ = 21.9%




Nicholas R. Lang
Manager, Research & Development Laboratory